# BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

## DRAFT TENDER SCHEDULE

**Issued to :**

**Original / Duplicate**

**Name of the work:- Pot hole filling to roads in ward no. 06 (Thanisandra) Byatarayanapura sub division.**

| Sl. No. | Quantity. | Description | Unit | Rates | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 1539.73 | KSRRB M300-2: Making up loss of material / irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment complete as per specifications | Sqm | 21.20 21.60 | |
| 2 | 230.96 | KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per MORTH specification | cum | 1713.96 | |
| 3 | 1539.73 | KSRRB 3000: Filling Pot-holes and patch repairs with ope-graded premix surfacing, 20 mm KSRRB M300-4, removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3 back filling the post holes with hot bituminous material as per clause 500.11 compacting, trimming and finishing the surface to form a smooth continues surface, all as per clause 3004.2 complete as per specifications, | Sqm | 370.44 | |

No of corrections - one

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92
13/02

"DTS Approved with one Correction as above."

Chief Engineer
Yelahanka Zone
Bruhath Bangalore Mahanagara
Palike
Bangalore 92